BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the Work : Providing and Fixing New Street Signage Boards in Ward No. 09, Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2.00	Providing and fixing ornamental name boards of size 2.10x0.50Mts and 2 Column of size 0.15x0.15 mts of hight 1.23 mts aof each board masde of C.C 1:1, 5:3 with necessary centreing and fromwork, smooth finishing with reinforcement etc including fabrication charges painting letters [BANGALORE MAHANAGARA PALIKE] earthwork excavation concreting and transportation charges from manufacturing yard to the site of work etc complete with all lead nad lift laoding ans unloading and executing as per the direction of the Engineer-in-charge	Each	6200.00	
2	343.00	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 2mm thick firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60 cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., as per the detailed specifications, drawings and directions of the engineer in charge of the work.	Each	4957.20	
3	0.58	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m. In depth with lead upto 50m. after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	227.88	
4	0.58	Loading and unloading ofstone **aggregates / sand/ kanker/ Moorum /soil** KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 117 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M etc complete as per specifications and directions of engineer in charge of the work	cum	72.71	

Exe.Engr.
Bip. Dn.

Name of the Work : Providing and Fixing New Street Signage Boards in Ward No. 09, Byatarayanapura Sub Division.

5	0.20	Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5323.32	
6	342.18	Painting lines, dashes, arrows etc, on roads in two coats on new work :- painting lines, dashes, arrows etc on roads in two coats on new work with ready mixed road marking paint conforming to IS:164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at the and traffic control complete as per specification, i) over 10 cm in width,etc complete as per specifications and directions of engineer in charge of the work	Sqm	108.00	
7	50000	Painting new letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification etc complete as per specifications and directions of engineer in charge of the work	Cm	0.65	

Signture of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92